

CASE STUDY: CRYSTAL PALACE PLATFORMS 1 & 2

Project Scope:

Realignment of new and existing copers and platform resurfacing

Client: Volker Rail

Duration: 2 Weeks

SCOPE OF WORKS:

The project involved comprehensive platform improvement works. This included the removal of existing mortar beds and platform walls, followed by the construction of new brick front walls. Copers were realigned to enhance platform stability, and new tactile paving was installed to improve accessibility and safety. Fresh white lining was applied to provide a clean, professional finish

OUTCOME:

Additionally, the works comprised 90 linear meters (Lm) of coping adjustments, 55 Lm of tactile paving installation, 30 Lm of platform front wall reconstruction, and the resurfacing of 200 square meters of the platform area. These upgrades significantly improved the platform's functionality, safety, and overall appearance.

